



Hungary / Devecser

# Grain Terminal and Processing Plant

Grain handling capacity: 60 t/h | Drying capacity: 2 x 25 t/h



Grain Terminals and Dryer Houses

**Year:** 2012

**Capacity and Designation:** Grain processing line with special regard to grain drying and cleaning, installed equipment is a 2 x 4000-25DU dryer, 4 cleaners and complete conveyor technology

- Corn drying capacity: 2 x 25 t/h (from 24% to 14%)
- Grain handling capacity: 60 t/h
- Flat storage house capacity: 2 x 4,000 t

**PETKUS Service:** Engineering and design of the general layout including flow-charts; project drawing and schematic diagrams, equipment lists, detailed machine and technology delivery and description and commissioning.