



Italy/Piubega

Corn Plant for Cleaning, Drying and Storing

Storage capacity: 24,000 MT | Cleaning capacity: 200 t/h



Grain Terminals and Dryer Houses

Year: 1996, 1st extension in 2003, 2nd extension in 2013

Capacity and Designation:

- Storage capacity: 24,000 t
- Conveying capacity: 200 t/h
- Pre-cleaning capacity: 100 t/h
- Cleaning and processing capacity: 60 t/h
- Dryer capacity (4 pcs): 200 t/h

Standards: DIN

PETKUS Service: Project design and project management with engineering and design of the general layout and flow-chart of the whole silo plant installation. Design of architectural drawing for the civil works calculation and realization. Delivery and installation of the silo plant including conveyors, steel silos, dryers, steel support frame and machinery house.