

Philippines/Rosalis

Corn Cob Dryer House and Calibration Line for Maize

Dryer house capacity: 500 t / Processing capacity: 10 t/h



Year: 2017

Capacity and Designation:

Double-pass dryer house with 10 drying chambers (8 x 115 m³ & 2 x 57,5 m³), modular galvanized steel construction with roof, incl. conveying technology, fan and burner as well as control system, sensors and illumination; Processing and calibration line with intake, pre-cleaner, fine cleaner, gravity table, continuous treader as well as bucket elevators and pendulum bucket elevators

- Dryer house capacity: 500 t / 1025 m³
- Processing capacity: 10 t/h

PETKUS Service:

- Engineering and design of the general layout including flow-charts, project drawings and schematic diagrams, equipment list, detailed machine and technology descriptions and documentation
- Delivery, assembly, installation, commissioning and training of the operating personnel